



INTERIOR JAMB AND DOOR SYSTEM K/D PRE-FIT

What is this system, and how will it help you?

- 1. Half-hinges factory applied to both jamb and door.
- 2. Factory applied casing and stop
- 3. Pre-machined doors and frames
- 4. Pre-notched to interlock
- 5. Drop-in pin





Contractors use knockdown systems in light commercial and residential applications. You receive the door and frame pre-machined and pre-fit; with half-hinges factory applied to the jamb and the door. Jamb legs and jamb head are notched for an interlocking fit. Haley ships the jamb in 3 pieces, handed jamb-legs packaged together and jamb head all with factory mitered and applied casing and stop.

Jambs and casing are primed M.D.F.; and raw or primed finger-joint. Doors are prefinished, primed, or raw; depending on the specification.

Just snap the 3 interlocking jamb pieces in the opening; place the door in the opening; drop the pin in the hinges; and staple through the casing!

Benefits:

- Material cost for K/D units can save up to 25% compared to pre-hung units --- you increase your profit margins.
- Freight costs from the factory to you are dramatically less, and your subsequent delivery costs to job-site are less --- you save cost on transportation twice --- inbound and outbound.
- The worker installs about 12 doors per hour (versus 6 for pre-hung?) --- the contractor saves money and you get a satisfied customer.
- Everyone requires dramatically less space to store and transport the material.
 Imagine delivering 80 jambs and 80 doors to jobsite on 2-1/2 pallets! --- all parties save money and storage space.
- Less damage to materials:
 - > At your warehouse.
 - > During delivery to jobsite.
 - On the jobsite.
- The installer uses the door to square-up the opening for nearly perfect reveals in all job-site conditions --- the building owner likes the finished look of his doorways, and you eliminate extra trips to the jobsite.

Stock Jambs:

 Wall Condition: minimum width 3-9/16" 7-1/4" maximum

Head Width: minimum 1 8' maximum

4'

minimum height Jamb Leg: 8' maximum

Hinge Preps.: 2, 3, or 4

Lead Times: shipment 2 - 3 weeks

please call for exact

• Pricing: please call for quote

Non-Stock Jambs:

3-9/16" Wall Condition minimum width

> 7-1/4" finger-joint, raw maximum

10" primed M.D.F

Head: minimum width 1' 8'

maximum

• Jamb Leg: 4' minimum height maximum 8'

Minimum Qty.: 50 openings

Lead Times: call for estimate

• 20-Minute: no

Doors In a K/D Pre-Fit System:

• Hollow Core: 1-3/8" half-hinge applied

lock prep

all hardware preps

1-3/4" half-hinge applied

lock prep

all hardware preps

• Solid Core: 1-3/8" half-hinge applied

lock prep

all hardware preps

1-3/4" half-hinge applied

lock prep

all hardware preps

Finishes Available:

• Jambs: medium-density fiber (M.D.F), primed

finger-joint pine, raw or primed

• Casing: medium-density fiber (M.D.F), primed

finger-joint pine, raw or primed

• Doors: pre-finished, primed, or raw; depending on specification

Hinges Available:

• US3LB Brass: 3-1/2" x 3-1/2" with 5/8" radius, reversible

• US26D Brushed Chrome: 3-1/2" x 3-1/2" with 5/8" radius, reversible

• Special Order: call for information

HBL-400.1.0 P-12



INTERIOR KD JAMB UNIT

FRAMES FURNISHED WITH 3-1/2" RADIUS CORNER HINGES APPLIED 4-9/16" WALL SHOWN. ALSO AVAILABLE FOR OTHER WALL SIZES.

